ATTACHMENT A

C.1.a.
Power pole on E. Alvarado to remain in place. Proposed 6” AC berm to replace proposed curb, gutter and sidewalk curb return improvements to Summit Avenue. Berm to extend around existing power pole and connect to existing edge of pavement approximately 29 feet west of power pole. No curb, gutter and sidewalk improvements. Existing fencing to be relocated to the right-of-way line.

C.1.b.
Proposed curb, gutter and sidewalk improvements. Power pole roughly 80 feet south of E. Alvarado on Summit Avenue to be relocated behind proposed sidewalk. Power pole roughly 75 feet north of W. Fig to remain. Sidewalk to leave curb southerly of pole, extend behind pole and rejoin curb northerly of said pole. Existing fencing to be relocated to the right-of-way line. Exception request is to waive undergrounding requirement only.